



DCN DIVING VAN

GENERAL INFO

Type

Mobile Air Diving System

Year of Build

2020

Number of Divers

2x Main Divers

1x Standby Diver

Standard

Build according to IMCA D040

Comms and Recording

Novasub SCC2DRVLDSPDVR

Specifics

Separated Control Room from Diving area

2x KM Morgan Diving Hats

1x KM Bandmask

2x 100 meters umbilical length

Compressor including air cylinders

Full Medical Kit Mad-A and First Aid

HP Waterjet, Underwater Cutting and Welding systems in place



