



**Location:** *China*

**Water Depth:** *10m*

**Date:** *2013*

**DCN Supply:**

- *Concept engineering*
- *Design and supervision of the construction of the cofferdam*
- *Development of the welding procedures in conjunction with The Welding Institute (TWI)*
- *Certified welding personnel, field engineers and offshore project management*

**Details of Work:**

*Cracks on 2 nodes of the legs of the platform needed repair following a failed topside package installation. For Class approval, the repairs needed to be undertaken in dry, controlled conditions to specific procedures.*

